

**TG05.2R - Site Logistics Temporary Power**

<b>Question No.</b>	<b>Submission Date</b>	<b>Question</b>	<b>Response</b>
TG05.2R-0001	3.29.2011	Please provide AIC rating for the (5) five 2500 Amp temp. switch boards.	All overcurrent protective devices within equipment must be able to clear a fault without extensive damage to the equipment itself, as required by the NEC. Therefore, it is the responsibility of the design engineer of the switchgear/switchboard manufacturer/supplier retained by the successful bidder to determine the required AIC rating.